



FRONT ELEVATION/SECTION

## KEY

- ① SET TREE PLUMB IN PLANTING PIT.
- ② PROTECT TREE TRUNK WITH 1 NOMACO® STYROFOAM PADDING GUARDS, #6U048048, AS SPECIFIED, OR APPROVED EQUAL.
- ③ AMAZON HOUSE AND RUBBER®. 1 ¼" AIR HOSE #K1146 OR APPROVED EQUAL, TO COVER 10 GAUGE WIRE.
- ④ 1 10 GAUGE GALVANIZED WIRE. WIRE PRODUCT®, OR APPROVED EQUAL.
- ⑤ 1 2"x4"x4' NON TREATED LANDSCAPE TIMBER AS SPECIFIED. FASTEN WITH 4 3½" DECK SCREWS TO 2"x4"x8' P.T. LANDSCAPE TIMBERS.
- ⑥ 1 ⅝" MALLEABLE CLAMP FASTENER FOR WIRE. SUPPLIER: FLORIDA WIRE® OR APPROVED EQUAL.
- ⑦ 2 2"x4" X 8' P.T. LANDSCAPE TIMBER AS SPECIFIED.
- ⑧ 1"-2" MULCH DEPTH LAYER ON ROOT BALL.
- ⑨ 4" WATER RING, (WITHIN ROOTBALL DIA.), FILL 3 TIMES IMMEDIATELY AFTER PLANTING, RAKE OUT PRIOR TO MULCHING AND PLANTING.
- ⑩ ROOT FLARE 1"-2" ABOVE FINISHED GRADE.
- ⑪ B#B OR CONTAINERIZED ROOTBALL. REMOVE ALL BURLAP IF NOT 100% BIODEGRADABLE. REMOVE CONTAINER FROM ROOTBALL PRIOR TO PLANTING.
- ⑫ BACKFILL. TOP SOIL TYP. OF AREA. BACKFILL SHALL BE AMENDED THROUGHOUT ENTIRE SITE WITH FERTILIZER AND COMPOST AS REQUIRED.
- ⑬ UNDISTURBED SUBGRADE.
- ⑭ COMPACT SOIL IMMEDIATELY BENEATH THE ROOT BALL TO PREVENT SETTLING.

### NOTES :

1. CONTRACTOR TO ASSURE PERCOLATION IN TREE PITS.
2. NO MULCH WITHIN 4" OF TRUNK.

TYP. MEDIUM TREE STAKING

(2½"-5" CAL.)

SCALE: N.T.S.